




**FP PREIS® SML in combination with:**

**Waterflow [Liters/Second]**

**0,5      1,0      2,0      4,0**

	0,5	1,0	2,0	4,0	Sound level in the ground floor (behind wall - "UG hinten") in [db(A)]
pipeclamp without rubber 	21	26	31	36	
pipeclamp with rubber 	16	20	25	30	
pipeclamp without rubber + vibration-decoupling element 	<10	<10	12	15	
Freestanding downpipe. <b>No fixation to the wall.</b> Downpipe only rests at the downpipe support. This figure shows only airborne sound, no structure borne sound. <i>(Not an official test result - for informational purposes only)</i>	-1	1	5	10	